



## **ADDENDUM NUMBER 2**

To the Contract Documents  
For the Construction of

**COMMUNITY DAY SCHOOL (Re-Bid)**

**Bid No. F13-04R**

**For**

**SAN BERNARDINO CITY UNIFIED SCHOOL DISTRICT**

March 19, 2014

### **NOTICE TO BIDDERS**

*It is intended that all work affected by the following provisions shall conform to the original plans and specifications. Delete or modify each of the following items wherever appearing on Drawings, and/or Specifications. Acknowledge receipt of Addendum No. 2 in the space provided on the Contractor's Proposal. Failure to do so may subject bidder to disqualification.*

### **DRAWINGS:**

**Item Number 1;** Reference sheet E-1.2, detail A – Enlarge Site Electrical Plan; Add six (6) plenum rated Cat 6 data cables from the IDF/MDF to each classroom. Run drops in classrooms in non-metallic raceway and terminate in data outlets. Wall location to be determined. Contractor is responsible for terminations of cabling and testing per Specification Section 16750.

Note: For reference only, the MDF is in the Electrical Room in the Admin building. The IDF is in Classroom building B5. MDF and IDF provided by District.

End of Addendum 2

  
**Ralph Pacini,**  
**PCH ARCHITECTS, LLP**